

## INVITATION TO BID

Notice is hereby given that

Wyandotte Public Schools

Will accept bids from qualified contractors for the project of

### **Renovation of boys baseball field and diamond**

Any questions should be directed to

Bernie Bowers, Wyandotte Public Schools

734-260-6741

[Bowersb@wy.k12.mi.us](mailto:Bowersb@wy.k12.mi.us)

The scope of work includes:

125 tons of DuraEdge Classic, 2 pallets of DuraPitch Premium Mound Clay, 2 tons of ProSlide Topdressing, 1 pallet of Playball Conditioner, up to 7,000 Square Feet of Sod, 50 tons of Topsoil, Pitching Rubber, 25 tons of Limestone Screenings, Home Plate, Bases, Anchors, 2 Portable Pitching Mounds, and Professional Installation Services

- Measure and mark field for square and lip removal.
- Lip removal measured at 10' outside of arc and foul, 6' outside of the infield grass transition, 8' around pitcher's mound, and 6' around home plate circle.
- Laser grade removed lip area to allow installation of new sod.
- Remove and dispose of any contaminated material in the process of creating positive surface drainage. •Distribute and install DuraEdge Classic Infield Mix, bringing the field to finish grade.
- Remove sod at 7' width to create basepaths and install DuraEdge Classic Infield Mix.
- Bring home plate area to grade and install DuraPitch Premium Mound Clay to batters' boxes and catcher's box.
- Set pitching rubber to 10" above home plate and install DuraPitch Premium Mound Clay to the table and landing area. Use DuraEdge Classic Infield Mix to promote proper shape.
- Topdress with ProSlide Topdressing and PlayBall Conditioner.
- Groom and prep for play.
- Measure, mark, and remove to a depth of 2" warning track area in front of both dugouts, including the addition of the on deck circle. • Install limestone screenings to the newly added warning track area in front of dugouts.
- Mark and clean home and away bullpen areas and grade to flat, allowing the use of a portable pitchers mound.
- Install sod to newly graded areas.

Notes: All leftover soil will be removed from the property by the contractor. Contractor is responsible for all measurements including square footage. Owner is responsible for all

irrigation work including relocating of existing heads. Owner is responsible for the watering and growth of new sod.

Work must be completed by September 30, 2026

Sealed bids will be received at the Board of Education for Wyandotte Public Schools, Operations Office, 639 Oak Street, Wyandotte, Michigan, 48192, until 1:00PM MONDAY, MAY 18, 2026. At that time, bids will be publicly opened. Bids received after the date and time specified will be returned to the bidder unopened.

The Owner reserves the right to reject any or all bids and to waive irregularity in the bidding or the bidding process and accept the bid that is most advantageous to the Owner.