



DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET  
 State Facilities Administration  
 Design and Construction Division

## CONSTRUCTION BID ADDENDUM NO. 2

This form identifies an Addendum to Bidding Documents, and incorporates interpretations or clarifications, modifications, acceptance of proposed "or equal" materials, and other information into the Bidding Documents. Addenda will be numbered by the Professional and distributed through [www.michigan.gov/SIGMAVSS](http://www.michigan.gov/SIGMAVSS) as an attachment.

TO: <b>ALL BIDDERS</b>		DATE ISSUED 4/24/2026
PROJECT NAME Saginaw Correctional Facility – Sewer Screening		FILE NUMBER 472/25355.CTS
PROFESSIONAL NFE Engineers	PROJECT DIRECTOR Chris Schanbeck	BID OPENING DATE: 4/29/2026

ADDENDUM ITEMS: (attach additional sheets and drawings if required)

1. Bidder Questions below:

Provide updated arc-flash model for facility. Would this be required since we are not furnishing any new Distribution Equipment?  
 Ans) Due to the rework of the feeders, a revised arc flash study will be required per code.

It's understood that M.E.P. permits are to be carried by the contractor via LARA. Is a building permit also required by the contractor?  
 Ans) No

1. Drawing (C2) indicates that contractors shall perform pre-construction cleaning and televising (CCTV) of existing sanitary sewer lines and flow channels thru the screening building, where noted. The leaders note sewer inspection from MH-1180 to Wet Well, MH-1180 to MH-1999, and from MH-1999 to Screening Building, for approximate total of 162 LF of existing 12" sanitary piping.
- Is there any sewer pipe that needs to be inspected inside (or thru) the Screening Building, like the note indicates?  
 Ans) Yes; the intent is to televise the flow channel to the screening equipment and then from equipment out of the building.
  - Does existing pipe get inspected from Wet Well north, to sanitary manhole in driveway?  
 Ans) Yes
  - Does existing pipe get inspected from driveway manhole north, to flow meter manhole?  
 Ans) Yes
  - Does existing pipe get inspected from flow meter manhole north to manhole at Pierce Road right-a-way?  
 Ans) Yes
  - Does existing pipe get inspected south of MH-1180?  
 Ans) No

ACKNOWLEDGEMENT: This Addendum must be acknowledged by the Bidder in the space provided in the Bid Summary and Bid Form. Failing to acknowledge Addenda may be cause for the Bid to be rejected. Addenda will become part of the Contract Documents.

Steve Sutton PROFESSIONAL: APPROVED BY:	DATE: 4/24/2026
PROJECT DIRECTOR: Chris Schanbeck	DATE: 4/24/2026